Brief delivery declaration – House on wheels 31

- Turnkey mobile house on wheels, can be transported as “efterfordon” (Swedish traffic rules).
- Equipped kitchen with fridge / freezer, cooktop, oven and fan hood (Electrolux). Selection of kitchen doors, countertops and splash guards (laminate) available as standard options.
- Equipped bathroom with sink cabinet and mirror cabinet with storage, shower corner (glass), WC (dry), towel dryer, bathroom fan, wet room floor tiles (light grey) and wet room wall tiles (white).
- Interior surface layers: White painted wood panel wall / ceiling; laminate floor (natural).

Construction facts

- Beams: Exterior wall 120 + 45 mm insulation; roof 195 mm insulation (external surface layer: Classic tin plate); floor 195 mm insulation (wooden joist floor).
- Windows and window doors: White PVC (3-glass).
- Staircase to loft, with storage / wardrobes under staircase.
- Complete electrical installation, incl. central box, spotlights ceiling, exterior lights, radiators and electric floor heating in wet room. Ventilation fans (K7).
- Fireplace.
- Complete water and plumbing installation in bathroom and kitchen, porcelain, mixers and water tank.
- Exterior wall panel painting (optional color according to RAL color code).
- Transport lights for “efterfordon” (Swedish traffic rules).

Price turnkey

Please refer to the price on each individual house. Transport is included.

For more detailed facts regarding the delivery and construction of houses please contact us.

Changes and options to this delivery declaration are offered upon request.

© 2024 Panteon Hus, www.panteonhus.se